



Report Number: 18-001188

Revision Number:1

Date Order Received: 02/27/2018

For the account of:

Vescom America Inc. 2289 Ross Mill Road Henderson, NC 272537

Client's Identification: Zanzibar Test #600

CERTIFICATE OF TESTING

TEST PERFORMED: Colorfastness to Wet & Dry Crocking AATCC 8-2016

TEST RESULTS

Rating

Wet Crocking Class 4.5
Dry Crocking Class 5.0

RATING SYSTEM

Class 5 No color transfer
Class 4 Slight color transfer
Class 3 Moderate color transfer
Class 2 Considerable color transfer
Class 1 Much Color transfer

NOTES

Scale Used for Evaluating: AATCC Chromatic Transference Scale

ACCEPTANCE CRITERIA

A.C.T. Standard

Upholstery	Class 4 minimum	Class 3 minimum
Direct Glue Wallcoverings	Class 3 minimum	Class 3 minimum
Panels and Upholstered Walls	Class 3 minimum	Class 3 minimum
Drapery (Solid)	Class 4 minimum	Class 3 minimum
Drapery (Print)	Class 4 minimum	Class 3 minimum

Acceptance Criteria (Dry)

CERTIFICATION I certify that the above results were obtained after testing specimen in accordance with the procedures and equipment specified by the standard stated above.

Chelsea hybrishe

Authorized Signature Date Order Completed: 03/02/2018

Acceptance Criteria (Wet)